









22nd Avenue Alternative Comparison

		Business 53	Prairie View	Total
ALTERNATIVE A	Intersection Control			
	Construction Cost			\$2,670,000
	R/W (SF)	54,760 SF	119,415 SF	174,175 SF
	LOS (Delay)	Overall: B (10.7 sec)	Overall: A (6.9 sec)	
ALTERNATIVE A	Intersection Control			
	Construction Cost			\$2,340,000
	R/W (SF)	54,690 SF	118,275 SF	172,965 SF
	LOS (Delay)	Overall: A (7.3 sec)	Overall: A (6.9 sec)	
ALTERNATIVE B	Intersection Control			
	Construction Cost			\$1,880,000
	R/W (SF)	44,735 SF	65,595 SF	110,330 SF
	LOS (Delay)	Overall: B (10.7 sec)	Overall: A (6.9 sec)	
ALTERNATIVE B	Intersection Control			
	Construction Cost			\$1,520,000
	R/W (SF)	44,735 SF	65,595 SF	110,330 SF
	LOS (Delay)	Overall: A (7.3 sec)	Overall: A (6.9 sec)	

NOTE: Operational analyses are based on 2033 PM peak hour traffic forecasts utilizing a 2% background growth rate, these forecast DO NOT include potential new large developments.